



Tree Preservation Plan (where applicable)

1. Submit five (5) copies of the tree preservation plan.
2. The following items must be on the plan that is submitted for review by Village Forester. (The Village may provide that the tree survey exclude those portions of the site that are determined not to be affected by development activity.)
 - A. For each tree six inches (6") diameter breast height (DBH) or larger, the Plan shall show:
 - 1) Location
 - 2) Species
 - 3) Trunk diameter DBH (diameter at breast height)
 - 4) Condition
 - B. The plan shall distinguish between:
 - 1) Existing trees that are proposed to be:
 - ☐ Preserved at their present location
 - ☐ Destroyed
 - ☐ Relocated
 - ☐ Replaced
 - 2) Trees introduced into the development from an off-site source must be:
 - ☐ Identified on the plan, OR
 - ☐ Identified in the accompanying landscape plan
 - C. Construction envelope - Identify locations of the required tree protection/construction envelope and erosion control fencing on the plan.
 - 1) The tree protection/construction envelope fencing must run continuously along the frontage from property line to property line to completely separate the construction area and the vegetation that remains close to the construction site.
 - 2) Separate fencing may be required for identifying conservation easements. This fencing must connect to the construction envelope fencing, a property line, or completely enclose the sensitive areas.
 - 3) Limits of construction will be staked and reviewed in the field by the Village Engineer and Village Forester prior to any clearing or site work.

NOTE: All fencing will remain in place until the time of finish grading and landscaping and can only be removed upon review and approval by the village Forester.

- D. An action description indicating the specific pre-construction measures, including but not limited to auguring, root pruning, crown reduction, overhead clearance pruning, and mulching that are to be taken to minimize construction impact on those trees remaining on the site shall be determined by the village Forester.
- E. Indicate areas for the storage of spoil or materials on the plan.

The Village Forester is:

*Chuck Steward or Todd Sinn
Urban Forest Management, Inc.
960 Route 22
Suite 207
Fox River Grove, IL 60021
Phone: (847) 516-9708
Fax: (847) 516-9716*

Plan Notes For Tree Preservation: ***(must be shown on plans)***

1. Prior to commencement of any grading or construction work on this site, the protective fencing shall be reviewed by the Village Forester.
2. All work must be performed according to the approved Tree Preservation Plan.
3. An approved Tree Preservation Plan must be available on the building site.
4. Stay within the designated work access areas shown on the plan.
5. There shall be no grading or filling within the protected critical root zones of protected trees.
6. No equipment shall be driven over or material stored on the critical root zones of protected trees.
7. Tree fence and silt fence for all protected trees must be properly maintained throughout construction.
8. All required tree and silt fencing shall remain in place until the time of finish grading and landscaping and can only be removed upon review and approval by the Village Forester.
9. Attachments (wires, fences, etc.) Other than those approved for guying, bracing or wrapping must not be attached to protected trees.
10. All excess fill material shall be removed from the site or stored in a location approved by the Village Forester.
11. Complete Action Plan Description for each tree impacted or removed.

Wooded Lots

Site Preparation - Pre-Construction

1. Tree Removal - Protection
 - A. Obtain a Building Permit
 - B. Clear the site of trees indicated for removal on the approved Site Development Plan and perform root pruning, crown reduction, auguring and all other measures as required on the approved plan.
 - C. Erect tree protection construction envelope and conservancy area fencing according to the following requirements:
 1. No attachments, fences or wires, other than approved materials for bracing, guying, or wrapping, shall be attached to any vegetation during the construction period.
 2. All fencing must be secured to metal posts driven into the ground spaced no further than ten feet (10') apart.
 3. All fencing must remain in place during the entire construction period.
 4. All fencing must run continuously from property line to property line, completely enclose an area, or adjoin other fencing in order to protect the vegetation that is to remain on site.
 5. Erect erosion control measures per approved plan requirements.
2. Site Visit
 - A. A site visit by the Village Forester is again required after the above items have been completed.

This document was created with Win2PDF available at <http://www.daneprairie.com>.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.